

# HENDERSON PARK LOOP TRAIL

## EXCAVATION SPECIFICATIONS

In 2017 Shiawassee County received a grant from the DEQ to make improvements to Henderson Park. This grant ends on December 31, 2021. The Shiawassee County Parks Commission is requesting bids to install an 850 foot long, 8-foot-wide limestone trail near the east side of the park and along the south side of the park, as shown on the location map, to connect to an existing trail. This contract is to excavate the trail, remove the spoils to a location in the park and compact the trail to prepare it for the installation of the limestone trail material.

The centerline of the trail will be laid out by the engineer. The contractor shall excavate the trail 6" deep and 8 feet wide along this centerline. The bottom of the excavated trail shall be rolled to compact any loose material. The excavated material shall be immediately loaded on to a truck and taken to the area designated for the spoils. This work shall be completed by December 24, 2021.

### BID PROPOSAL

WORK ITEM	QUANTITY	PRICE	TOTAL
Excavate 8' wide trail	Lump Sum		
		Total Bid	

Bidder's Signature \_\_\_\_\_

Date: \_\_\_\_\_