

HENDERSON PARK LOOP TRAIL

TRAIL MATERIAL PLACEMENT SPECIFICATIONS

In 2017, Shiawassee County received a grant from the DEQ to make improvements to Henderson Park. This grant ends on December 31, 2021. The Shiawassee County Parks Commission is requesting bids to install an 850 foot long, 8-foot-wide limestone trail near the east side of the park and along the south side of the park, as shown on the location map, to connect to an existing trail. This contract is to place and compact a uniform 4" thick layer of 23A limestone on the bottom of the existing excavated trail and to then place and compact a 4" layer of the limestone trail-mix on top of the base limestone. The final surface shall be graded to a uniform smooth walking surface to the approval of the engineer. The two limestone items will be supplied by the county and placed in separate piles on the existing gravel drive north of Henderson Road. This work shall be completed by December 24, 2021. There is approximately 150 tons of each material.

BID PROPOSAL

WORK ITEM	QUANTITY	PRICE	TOTAL
Place 4" of 23A limestone	Lump Sum		
Place 4" of Trail Mix	Lump Sum		
		Total Bid	

Bidder's Signature _____

Date: _____